4 CALA STREET - GEELONG ROAD

Improve recreation and connections



LEGEND

PATHS & ACCESS

- Existing 2.5m concrete shared path (Upgrade to 3m at time of renewal)
- Proposed concrete shared path
- Proposed new sections of bike lane 1.5m wide

PARK INFRASTRUCTURE

- Existing park seat
- Proposed park seat
- Existing picnic table
- Proposed picnic table
- Proposed wayfinding sign
- Existing maintenance vehicle access gate
- Proposed maintenance vehicle gate
- Existing playground

TREES, PLANTING & SOFT LANDSCAPE

- Proposed native trees planted in groups / copses of 3-7
- Proposed creek-side planting utilising native shrubs and semi-aquatics
- Proposed buffer planting with native shrubs and trees

CREEK & WATER QUALITY INFRASTRUCTURE

- Creek culvert - inaccessible to public
- Proposed raingarden for stormwater treatment

PRIORITY	ACTIONS	TIMEFRAME
HIGH	4.1 Increase tree and creek-side planting.	Short / ongoing
HIGH	4.2 Construct shared path from Waratah Street to Roberts Street. May include acquisition of adjacent property to ensure path access.	Short
HIGH	4.3 Advocate to VicRoads for cycling and pedestrian improvements to Geelong Road intersection	Short
MEDIUM	4.4 Expand A. MacDonald Reserve south into Council Nursery site. Remove existing chainmesh link fence. Develop basic parklands with grass and trees for kickabout space	Short
LOW	4.5 Construct the Bassett Reserve raingarden for stormwater treatment	Long